Appendix 3A-5: Summary of Annual Flows and Total Phosphorus Loads by Structure for Water Year 2008

Shi Kui Xue

Table 1. Annual flows and total phosphorus loads by structure forWater Year 2008 (WY2008) (May 1, 2007–April 30, 2008).

Into STA1 Inflow Basin					
0.t	Flow	Phos	phorus		
Structure	1000 ac-ft	Load (kg)	FWMC (ppb)		
S5A_P	126.136	25,662	165		
S5A from EAA	117.970	21,031	145		
S5A from East Beach	7.116	4,534	517		
S5A from Lake	0.252	56	181		
S5AW from Lake	0.000	0	n/a		
S5AW from L8 Basin	0.023	2	62		
Mass Balance Adjustment	0.775	39	41		
S5AS	0.884	197	181		
S5AS from Lake	0.884	197			
S5AS from L8 Basin	0.000	0			
G300	42.781	2,012	38		
G301	67.970	3,545	42		
G311	16.880	2,518	121		
Total	254.651	33,934	108		

	Flow	Phosphorus			
Structure	1000 ac-ft	Load (kg)	FWMC (ppb)		
S-5AS	152.786	10,643	56		
From S-5A	26.921	2786	84		
from EAA	25.182	2273	73		
from East Beach	1.519	490	262		
from Lake	0.054	6	91		
from L8 Basin	0.005	0	3.		
From WCA-1	88.076	3,653	34		
From G-311	10.589	752	58		
Mass Balance Adjustment	-19.445	-2693			
Net S-5AS	133.341	7,951	48		
G-300	0.000	0	n/a		
G-301	0.000	0	n/a		
G-302	116.291	26,574	185		
From S-5A	90.513	21455	192		
from EAA	84.665	17504	16		
from East Beach	5.107	3774	59		
from Lake	0.181	47	21		
from L8 Basin	0.017	1	7.		
From WCA-1	12.219	671	45		
From G-311	2.797	280	81		
Mass Balance Adjustment	-4.860	-2271			
Net G-302	111.431	24,303	217		
G-311	14.502	3,176	178		
From S-5A	8.684	1538	144		
from EAA	8.123	1,254	12.		
from East Beach	0.490	270	44		
from Lake	0.017	3	15		
from L8 Basin	0.002	0	5.		
From WCA-1	1.215	72	48		
Mass Balance Adjustment	-3.867	-1340			
Net G-311	10.635	1,836	163		
Total	255.408	34.090	108		

	Flow	nhorus	
Structure	1000 ac-ft	Load (kg)	FWMC (ppb)
G300 & G301	0.000	0	n/a
from FAA	0.000	- 0	n/a
from East Beach	0.000	0	n/a
from Lake	0.000	0	n/a
from L8 Basin	0.000	0	n/a
From WCA1	0.000	0	n/a
from G311	0.000	0	n/a
Mass Balance Adjustment	0.000	0	11/4
S362 (from STA-1E)	125.391	3,138	20
from EAA	8.935	224	20
from East Beach	0.539	13	20
from Lake	0.019	0	20
from L8 Basin	0.188	5	20
From WCA1	1.359	34	20
from G311	0.003	0	20
C51W	101.652	2.544	20
From S361	11.710	293	20
Mass Balance Adjustment	0.986	25	71
G251 (from STA-1W)	0.418	262	508
from EAA	0.317	199	508
from East Beach	0.019	12	508
from Lake	0.001	0	508
from L8 Basin	0.000	0	508
From WCA1	0.046	29	508
from G311	0.010	7	508
Mass Balance Adjustment	0.024	15	508
G310 (from STA-1W)	116.584	7,349	51
from EAA	88.579	5,584	51
from East Beach	5.343	337	51
from Lake	0.189	12	51
from L8 Basin	0.018	1	51
From WCA1	12.784	806	51
from G311	2.927	184	51
Mass Balance Adjustment	6.743	425	51
ACME1 (from Basin B)	0.000	0	n/a
ACME2 (from Basin B)	0.000	0	n/a
Total	242.393	10,749	36

From WCA1			
Structure	Flow	Pho	osphorus
	1000 ac-ft	Load (kg)	FWMC (ppb)
S10A	17.021	357	17
S10C	25.289	514	16
S10D	59.536	1502	20
S39	0.353	7	15
G300	42.781	2,012	38
G301	67.970	3,545	42
G94A	0.557	15	22
G94B	0.006	0	42
G94C	0.267	7	20
Total	213.780	7,958	30

Into WCA2				
Structure	Flow	Phosphorus		
	1000 ac-ft	Load (kg)	FWMC (ppb)	
G335 (from STA-2)	227.003	6,085	22	
from EAA	211.476	5,669	22	
from East Beach	15.005	402	22	
from Lake	0.522	14	22	
Mass Balance Adjustment	0.000	0	22	
S7	159.353	3,817	19	
from STA 3/4	129.547	3,217	20 1	
From Lake O	0.174	4	20	
from EAA	123.454	3,046	20	
From C-139	0.736	18	20	
From SFCD	3.720	92	20	
From SSDD	1.464	36	20	
From G371	0.124	6	38	
from Lake O	0.000	0	38	
from EAA	0.124	6	38	
Back flow (S7(-)-G371(-) - G373(-)+G357(-))	17.867	419	19	
Mass Balance Adjustment	11.814	176	12	
S10A (from WCA1)	17.021	357	17	
S10C (from WCA1)	25.289	514	16	
S10D (from WCA1)	59.536	1,502	20	
N. Springs Improv. District	0.000	0	n/a	
Total	488.202	12,275	20	

Structure	Flow	Phosphorus	horus		
	1000 ac-ft	Load (kg)	FWMC (ppb)		
S7	107.901	1,992	15		
S11A (from WCA2)	103.975	1,074	8		
S11B (from WCA2)	119.464	2,750	19		
S11C (from WCA2)	180.365	2,544	11		
S38	0.706	8	10		
S34	0.000	0	n/a		
Total	512.411	8,369	13		

Into WCA3					
Structure	Flow	Phosphorus			
	1000 ac-ft	Load (kg)	FWMC (ppb)		
S140 (from L28 Canal)	90.340	4,046	36		
S190 (from Feeder Canal)	25.310	3,151	101		
G407	0.000	0	n/a		
S1A6	2.458	117	38		
58	20.852	561	17		
From STA3/4	21.830	542	20		
From Lake O	0.029	1	20		
FIOITIEAA	20.803	513	20		
From C-139	0.124	3	20		
From SFCD	0.627	15	20		
From SSDD	0.247	6	20		
From G373	1.661	98	48		
From Lake O	1.208	72	48		
From EAA	0.388	23	48		
From C-139	0.008	1	48		
From SFCD	0.028	2	48		
From SSDD	0.029	2	48		
STA5	2.035	240	96		
Back flow (S7(-)-G371(-) -	0.011	74	10		
G373(-)+G357(-))	3.011	200	19		
S150	-1.004	2 574	100		
from STA 3/4	90 713	2,574	20		
From Lake O	0 122	3	20		
From EAA	86 446	2 1 2 2	20		
Erom C-139	0.515	2,133	20		
From SECD	2 605	13 64	20		
From SSDD	1.025	25	20		
Erom G371	0.087	23	20		
from Lake O	0.007	4	30		
from EAA	0.000	4	20		
Back flow (SZ() G2Z1()	0.067	4	30		
G373(-)+G357(-))	10 511		10		
	12.511	293	19		
G404 & G357	0.273	1 / 15	10		
Erom STA3/4	54 072	1 3 4 3	20		
From Lake O to G409	0 072	1,545	20		
From EAA	51 528	2	20		
Erom C-139	0.007	1,2/1 Q	20		
From SECD	0.307	2.0	20		
From SSDD	0.611	15	20		
Erom C272	0.077	244	20		
FIOII 0373	2 993	177	40		
From EAA	2.000	57	40		
Erom C-139	0.900	J/ 1	40		
From SECD	0.021	1	40		
From SSDD	0.009	4	40		
STA5	5 040	7 596	96		
Back flow (S7(-)-G371(-) -	7,458	175	19		
G373(-)+G357(-))					
Mass Balance Adiustment	-4.171	-942	183		
S11A (from WCA2)	103.975	1,074	8		
S11B (from WCA2)	119.464	2,750	19		
S11C (from WCA2)	180.365	2,544	11		
G123 (from N. New River)	0.000	0	n/a		
S9 (from C-11 West)	52.632	1,282	20		
Total	867 292	1,523 21 037	20		
i otai	301.232	21,037	20		

Structure	Flow	Phosphorus	;
	1000 ac-ft	Load (kg)	FWMC (ppb)
S150	0.000	0	n/a
S8	0.000	0	n/a
S31	0.012	0	10
S337	64.390	1,010	13
S343A	0.000	0	n/a
S343B	0.013	0	15
S344	0.000	0	n/a
S12A	2.061	37	15
S12B	7.279	104	12
S12C	9.257	120	11
S12D	19.336	278	12
S333 ²	66.584	1,107	13
S355A/S355B	0	0	n/a
G409	9.162	539	48
Total	178.095	3,196	15

Into Everglades National Park

Structure	Flow Phosphorus				
	1000 ac-ft	Load (kg)	FWMC (ppb)		
S12A (from WCA3)	2.061	37	15		
S12B (from WCA3)	7.279	104	12		
S12C (from WCA3)	9.257	120	11		
S12D (from WCA3)	19.336	278	12		
S-333-S334 (from WCA3) ³	64.264	1081	14		
S355A/S355B (from WCA3)	0	0	n/a		
S174 (from L-31W)	0.000	0	n/a		
S332D	32.689	262	6		
S18C	124.381	1,163	8		
Total	259.267	3,046	10		
Total to EPA ⁴	1249.307	36,745	24		

From ENP

Structure	Flow	Phosphorus	
	1000 ac-ft	Load (kg)	FWMC (ppb)
S197	8.462	42	4
Total	8.462	42	4

FWMC = flow-weighted mean concentration

Total to EPA ⁴	1249.307	36,745	24	Total from EPA ⁵	296.439	9,161	25	
¹ The values are proportionally calculated based on summation of EAA model outputs of S7 and S8 Basins								
2								

² The value included S334 from WCA3.

³TP load was calculated using concentration at \$333 and flow of \$333-\$334.

⁴Total loads to the EPA are calculated from total of WCA1,2,3 and Everglades National Park subtracted \$10A,C,D; \$11A,B,C; \$12A,B,C,D; \$333-\$334 and \$355A/\$355B.

⁵Total loads from the EPA are calculated from the total from WCA1,2,3 for S39, G300, G301, G94A, G94B, G94C,S7, S38, S34, S150, S8, S31, S337, S343A, S343B, S344, S197, S333, subtracted S333-S334 (from WCA3 to ENP).